GridShield Financial Forecasting

Electric Load Optimization & Regulatory Risk Management

Author: Abinash Mohanty
Roll no.: 2305508
Classification: INTERNAL / HIGH PRIORITY

Executive Summary

This project establishes a robust, cost-aware electric load forecasting pipeline designed to minimize financial penalties incurred under asymmetric regulatory constraints. By evolving from a naive ML baseline (Stage 1) to a structurally recalibrated model (Stage 2) and finally a governance-compliant deployment (Stage 3), we have achieved a significant reduction in total penalty while ensuring 100% adherence to regulatory bias and reliability limits.

Key Optimization Results

Metric	Value	Status
Total Penalty Reduction	34.2%	SUCCESS
Peak Reliability (p95)	99.2%	COMPLIANT
Average Forecast Bias	1.24%	OPTIMAL
Governance Uplift Cap	3.0%	WITHIN LIMIT

Project Methodology

Our approach leverages a Random Forest architecture integrating historical load data with external factors including temperature, humidity, heat index, and public holiday events. The core innovation lies in the **Asymmetric Penalty Function**: penalizing under-forecasting at 6x (Peak) or 4x (Off-Peak) the rate of over-forecasting to prevent catastrophic grid instability.



Figure 1: Correlation Analysis between Load and External Weather Factors

Feature Engineering Priority

The model identifies 'Lag-96' (24-hour previous interval) and 'ACT_TEMP' as the primary drivers of demand. The inclusion of temporal features like 'day_of_week' and 'is_peak' allows for nuanced optimization.



Figure 2: Relative Importance of Model Input Features

Multi-Stage Evolution

Stage 1: Machine Learning Baseline

Initial focus on pure predictive accuracy using a Standard Random Forest. While accurate, the model was blind to the financial cost of errors, particularly the heavy penalty for under-forecasting during peak hours.

Stage 2: Structural Recalibration

Introduction of the 'Multiplier Sweep' strategy. We identified that a 1.5% upward buffer on peak-hour forecasts drastically reduced total penalty by converting expensive under-forecasts into cheaper over-forecasts.

Stage 3: Governance & Governance Compliance

Final refinement to ensure all strategic buffers remain within regulatory bounds. Constraints include: Max bias < 3%, Average Uplift < 3%, and no more than 3 instances of >5% peak under-estimation.



Figure 3: Total Penalty Reduction across Optimization Stages

Final Deployment Results



Figure 4: Optimized Stage 3 Forecast against Actual Load (Sample Period)

Risk Transparency: Worst Deviation Intervals

While the system is robust, we maintain transparency on extreme variance events. The 95th percentile deviation is tracked to maintain buffering adequacy.

Interval (Datetime)	Actual Load	Deviation	Factor
2024-03-12 19:30	4,245 MW	212 MW	Extreme Temp Spike
2024-03-15 20:00	4,310 MW	185 MW	Unexpected Event
2024-03-18 19:15	4,180 MW	160 MW	High Volatility
2024-03-20 21:00	4,450 MW	145 MW	Weather Shift
2024-03-22 18:45	4,090 MW	130 MW	Sensor Lag

Power BI Integration

The finalized forecasting dataset is exported via `PowerBI_Final_Dataset.csv` for real-time visualization in the GridShield Executive Dashboard. This allows for live monitoring of penalty exposure and model health.

Conclusion & Next Steps

The GridShield forecasting model successfully bridges the gap between machine learning accuracy and regulatory financial reality. By prioritizing peak-hour stability and adhering to strict governance buffers, we have secured a platform that is both profitable and compliant.